

Name: Tomi Williams

Student Number: 2506045

Unit: Assignment 1 Concrete Frame

Module Code: ACBA4016



Prifysgol Cymru
Y Drindod Dewi Sant
University of Wales
Trinity Saint David

Table of contents

Introduction	
Original design and method of construction.....	
Strength, Durability and Climate Resistance.....	
Time, Labour, Programme and Cost Compared with Steel Framing.....	
Ease of Assembly and Adaptation During the Building Life Cycle.....	
Integration of Building Services.....	
Challenges of Potential Demolition and End of Life.....	
Negative Impacts of Concrete Production on the Community and Environment.....	
Sieve Analysis Table and Particle distribution Graph.....	
Reference List.....	

The Reinforced Concrete Frame of the Burj Khalifa

Introduction

The Burj Khalifa in Dubai, provides an appropriate case study for examining the design, construction and life-cycle performance of a concrete framed building. Completed in 2010, the 830 metre tower is considered one of the most recognisable examples of high rise reinforced concrete construction. Designed by Skidmore, Owings & Merrill , with Adrian Smith as chief architect and William F. Baker as chief structural engineer, the building combines a reinforced-concrete primary structure with steel, aluminium and glass components. Its structural design was developed specifically to resist the extreme wind, temperature and ground conditions of Dubai while supporting its mixed use purpose of residences, offices, hotel accommodation and viewpoint facilities (SOM, n.d.). (Baker and Pawlikowski, 2015).



The Burj Khalifa is particularly valuable as a case study because its structural material was not selected simply as a conventional construction choice. The large vertical loads, the need for high stiffness against wind, the extreme desert climate and the logistical problems of constructing at great height all influenced the design of the concrete frame..

Original Design and Method of Construction

The original design of the Burj Khalifa was based on a three-winged, Y-shaped plan arranged around a central hexagon shaped reinforced-concrete core, the design was influenced by the shape of the Hymenocallis desert flower and by religious architectural patterns. Each of the three wings supports and stabilises the others through the central core, creating a highly stiff structure capable of resisting both gravity and lateral wind forces (SOM, n.d.).

The Y-shaped plan was fundamental to the building's performance because as the tower rises, the wings progressively step back in a spiralling pattern, these setbacks reduce the exposed building mass and hence shelters these points from high wind

speeds and force. This was particularly important because wind loading, rather than simply gravity loading, was one of the principal structural challenges associated with achieving the building's extreme height. This structural formation also allowed the vertical columns and walls to remain relatively continuous throughout, avoiding major transfer structures/link points which would have increased construction complexity (SOM, n.d.; Baker and Pawlikowski, 2015).

The foundation consists of a large reinforced-concrete raft supported by bored reinforced-concrete piles, the raft is approximately 3.7 metres thick and was constructed in four separate pours using approximately 12,500 cubic metres of concrete. The piles are approximately 1.5 metres in diameter and extend approximately 43 metres into the ground according to the official Burj Khalifa project information (Burj Khalifa, n.d.). The foundation design was especially important because Dubai's groundwater contains high concentrations of chlorides and sulphates, creating a potential risk for corrosion. This meant that concrete types had to be changed and protective measures were required to improve durability of the foundation.

The tower's primary structure contains approximately 330,000 cubic metres of concrete and approximately 39,000 tonnes of reinforcing steel, high performance concrete was used in the core and other heavily loaded structural elements. In November 2007, concrete was pumped to a height of approximately 601 metres something which had never yet been seen in the construction industry. The concrete was pumped using specialised high pressure equipment and was designed to remain workable for sufficient time to allow transportation, pumping and placement (Burj Khalifa, n.d.; Construction Week, 2014).


Dubai's climate created additional construction challenges, summer temperatures are extremely high, creating risks of rapid setting, cracking and loss of concrete performance. This meant that major concrete pours were undertaken during cooler night-time conditions, while ice and carefully controlled mix designs were used to reduce concrete temperature. The 3.7 metre thick foundation raft also required monitoring and heat control because excessive temperature gradients could have caused cracking resulting in structural and load bearing issues (Bester, 2013).

Strength, Durability and Climate Resistance

The strength properties of a reinforced concrete frame was a major reason why concrete was suitable for the project, concrete has excellent compressive strength, making it appropriate for the extensive vertical loads caused by a 830 metre tower. Reinforcing steel complements this characteristic by providing tensile capacity and helping the structural system resist bending and cracking. In the Burj Khalifa, the core based structural design enabled the concrete walls to function as a highly stiff system rather than relying primarily on a conventional beam-and-column (frame Bester, N. (2013)

The concrete was also required to resist the specific environmental conditions of Dubai, the building is exposed to intense solar radiation, very high temperatures and temperature fluctuations and airborne dust. The foundation is particularly vulnerable to aggressive groundwater containing chlorides and sulphates, the use of dense, low-permeability concrete reduced the movement of harmful substances through the concrete towards the reinforcing steel. The foundation and material choice therefore demonstrates how mix design and durability requirements were directly related to the specific site conditions of the building (Burj Khalifa, n.d.).

However, concrete is not immune to deterioration, thermal movement can create cracking, while the ingress of chlorides can cause corrosion if the concrete becomes damaged. High temperatures also create significant construction risks when using concrete, as illustrated by the need for night-time pouring and cooling methods during the Burj Khalifa project. The durability of the material and building itself therefore depends not only on the inherent strength of concrete but also on the quality of mix design, construction, waterproofing inspection and long term maintenance.



Time, Labour, Programme and Cost Compared with Steel Framing

The Burj Khalifa demonstrates that reinforced concrete can be highly competitive for extremely tall buildings, the concrete frame provided substantial stiffness and mass, both of which were valuable in resisting wind force on the building. A steel frame could have provided a lighter structure and potentially faster erection through prefabricated components, but it would have required extensive fire protection and would have offered different properties, some of which may not be suitable for a structure of this height and weight.

Using concrete was labour intensive and required large quantities of reinforcement, formwork, pumping and quality control, the project reportedly involved approximately 22 million man-hours of work, while construction costs were approximately US\$1.5 billion (Architectural Digest, 2024; Wikipedia, 2026). The construction programme ran from 2004 to completion in 2010. The use of repetitive formwork systems and structural designs helped make the construction process more efficient.

Compared with steel framing, reinforced concrete generally involves slower curing and greater dependence on site based operations, steel components can be fabricated off site and rapidly assembled, potentially reducing the construction programme. However, the Burj Khalifa's concrete system benefited from repetitive floor layouts and the use of high performance pumping technology reduced programme durations and cost. The concrete core and walls could be constructed progressively as the building rose.

Cost comparisons must therefore consider the whole structural system rather than simply the price of the material. Steel may reduce erection time but can involve substantial costs for fabrication, transport, fire protection and corrosion protection. Concrete requires cement, aggregates, reinforcement, formwork and significant labour. In the Burj Khalifa, the choice of concrete was ultimately justified by the structural efficiency and stiffness required for the tower's extreme height.

Ease of Assembly and Adaptation During the Building Life Cycle

The Burj Khalifa's concrete frame was relatively efficient to assemble because its structural design was repetitive and vertically organised, the Y shaped plan and repeated floor layouts allowed construction teams to use systematic formwork and sequencing methods amounting to “more than 3 million square feet of interior space”. The structure's regular load paths were also important because columns and walls could continue vertically without the need for extensive transfer structures (SOM, n.d.).

Nevertheless, reinforced concrete is less adaptable than a steel frame once constructed, steel beams and columns can often be removed, strengthened or rearranged more readily than heavily reinforced structural walls and slabs. The Burj Khalifa's central core is fundamental to its stability and contains major load bearing circulation and service infrastructure. This means that removing or significantly altering core walls would be extremely difficult without major temporary works and structural strengthening.

Adaptation is therefore more achievable at the level of internal fit out than at the level of the main structure itself, office floors can be reconfigured, partitions can be relocated and services can be modified. However, major changes to floor loading, structural openings or the buildings primary shape/structure would be difficult. This highlights that using concrete for the structural designs provides long-term durability but limits radical adaptation.




Integration of Building Services

The integration of services was a major challenge because the Burj Khalifa contains residential, hotel, office and observation facilities within a extremely tall structure, M&E systems had to be coordinated with the reinforced-concrete structure from the design stage. The tower includes seven double height mechanical floors containing equipment such as electrical substations, water tanks, pumps and air-handling systems (Burj Khalifa, n.d.).

Concrete structures create particular coordination challenges because services cannot simply be relocated through major structural components after construction, creating openings through core walls, slabs and beams must be carefully designed because excessive openings can weaken the overall strength of the building. The solution at the Burj Khalifa was early coordination between structural, mechanical, electrical and plumbing designers. Service floors were incorporated into the building's overall structural and architectural planning.

The building's height also creates major pressure and pumping challenges for water supply, the tower's water system supplies approximately 946,000 litres of water per day, while condensation from air conditioning systems is collected for irrigation water (Burj Khalifa, n.d.). The building therefore demonstrates that service integration in a complex concrete-framed building requires services to be treated as a fundamental part of the structural design rather than as systems added after the frame has been completed.




Challenges of Potential Demolition and End of Life

In the unlikely situation that the building required to be demolished, the Burj Khalifa would present exceptional demolition challenges. Its height, urban setting, reinforced concrete core and extensive foundations mean that conventional explosive demolition would be highly inappropriate because of the risk to surrounding infrastructure and the difficulty of controlling the collapse of such a large structure which could pose risk to life.

A more realistic approach would involve a carefully engineered top down deconstruction process, this is where Internal finishes, mechanical equipment and recoverable materials etc would first be removed. The structural concrete would then need to be broken down progressively using specialised high rise or remotely operated equipment. The steel used in the building could be separated and recycled, while crushed concrete could potentially be processed into recycled aggregate. However, separating concrete is energy-intensive, and may be seen as a wasteful process.

The foundation would be especially difficult to remove because of the large reinforced-concrete raft and deep piles. Possibly, some substructure elements might be left in place if their complete removal created greater environmental and structural risks than abandoning the material. Therefore, the Burj Khalifa project highlights an important disadvantage of reinforced concrete, its high durability and method of construction provide effective and efficient performance however make complete end-of-life demolition difficult.



The urban setting of the Burj Khalifa is highlighted in the image to the left gathered from my own primary research through a desktop survey. The Burj is in a highly built up area surrounded by national highways, tourist attractions etc.

Negative Impacts of Concrete Production on the Community and Environment


The environmental impact of concrete begins with the production of cement, the main binding material in concrete, cement manufacture requires the heating of raw materials to very high temperatures. Co₂ is released both from fuel combustion and from the melting of limestone itself. Cement production is therefore responsible for a significant proportion of global carbon dioxide emissions, with estimates commonly placing its contribution at approximately 4% of global emissions (Andrew 2018: IEA, 2024).


The scale of the Burj Khalifa makes this issue particularly significant, approximately 330,000 cubic metres of concrete were used in the tower, although concrete is made largely from aggregate, the volume of cement required represents a substantial carbon lifecycle for the building. The extraction of limestone and aggregates can also cause habitat loss, landscape alteration, dust generation and noise pollution. Water is required in concrete production and construction, which is especially difficult in Dubai, an area surrounded by desert environment.

There are also community impacts associated with the production and transport of concrete, quarrying and cement manufacturing can generate dust, noise and heavy vehicle movements, affecting the residential and commercial areas/communities surrounding the Burj Khalifa's site. During construction of the Burj Khalifa itself, the movement of large quantities of materials and the operation of pumps, cranes and construction equipment would have created noise, traffic and air-quality impacts also affecting the surrounding residents.

The environmental impact of concrete production for the Burj specifically can be compared against the long life of the building, the Burj Khalifa's durable reinforced-concrete structure will potentially remain in place for decades/centuries, spreading its

initial carbon lifecycle over a long period. Nevertheless, durability does not eliminate the initial environmental cost. Future improvements to the building could use recycled materials or more sustainable practices, these are important routes for reducing concrete sector emissions (IEA, 2025).





(IEA, 2024).

Practical work -

Sample Size: 1250g

Sieve Size (mm)	Mass(g)	% on sieve	% Passing
125	0	0	100
75	0	0	100
63	0	0	100
37.5	120	9.6	90.4
20	137	10.96	79.44
10	143	11.44	68
6.3	105	8.4	59.6
3.35	45	3.6	56
2	130	10.4	45.6
1.18	63	5.04	40.56
0.6	105	8.4	32.16
0.3	102	8.16	24
0.212	109	8.72	15.28
0.15	98	7.84	7.44
0.063	55	4.4	3.04

Fine and Coarse Aggregate Calculation


Coarse aggregate (>6.3 mm): Total = 505 g = 40.4%

Fine aggregate (<6.3 mm): Total = 707 g = 56.56%

Material loss: 3.04%

This sample is not suitable for structural concrete due to quality issues highlighted by the particle size distribution graph. It contains too much fine aggregate and insufficient coarse aggregate. This can lead to, strength issues, reduced durability, shrinkage, cracking and poor long term performance etc.

Particle Size Distribution Graph



Word Count: 2000 +/- 10%

References

Andrew, R.M. (2018) 'Global CO₂ emissions from cement production, 1928–2017', *Earth System Science Data*, 10, pp. 195–217. Available at: <https://doi.org/10.5194/essd-10-195-2018> (Accessed: 7 June 2026).

Architectural Digest (2024) 'Burj Khalifa: Everything You Need to Know About the Tallest Building in the World'. Available at: <https://www.architecturaldigest.com/story/burj-khalifa> (Accessed: 7 June 2026).

Baker, W.F. and Pawlikowski, J.J. (2015) 'The design and construction of the world's tallest building: The Burj Khalifa, Dubai', *Structural Engineering International*, 25(4), pp. 389–394. Available at: <https://doi.org/10.2749/101686615X14355644770857> (Accessed: 11 June 2026).

Bester, N. (2013) 'Concrete for high-rise buildings: Performance requirements, mix design and construction considerations', *Structural Concrete Properties and Practice*. Available through ResearchGate https://www.researchgate.net/publication/263889511_Concrete_for_high-rise_buildings_Performance_requirements_mix_design_and_construction_considerations (Accessed: 11th June 2026).

Burj Khalifa (n.d.) 'Structure and design'. Available at: <https://www.burjkhalifa.ae/the-tower/structures/> (Accessed: 27 July 2026).

Construction Week (2014) 'How the Burj Khalifa was built'. Available at: <https://www.constructionweekonline.com/projects-tenders/article-32805-how-the-burj-khalifa-was-built-updated> (Accessed: 11 June 2026).

International Energy Agency (IEA) (2024) *Breakthrough Agenda Report 2024: Cement*. Paris: IEA. Available at: <https://www.iea.org/reports/breakthrough-agenda-report-2024/cement> (Accessed: 11th June 2026).

International Energy Agency (IEA) (2025) *Breakthrough Agenda Report 2025: Cement and Concrete*. Paris: IEA. Available at: <https://www.iea.org/reports/breakthrough-agenda-report-2025> (Accessed: 12 June 2026).

Skidmore, Owings & Merrill (SOM) (n.d.) 'Burj Khalifa'. Available at: <https://www.som.com/projects/burj-khalifa/> (Accessed: 12th June 2026).

Wikipedia (2026) 'Burj Khalifa'. Available at: https://en.wikipedia.org/wiki/Burj_Khalifa (Accessed: 12 June 2026).

Images

Images of the Burj Khalifa being constructed included in the report was taken from the following - <https://www.burjkhalifa.ae/the-tower/architecture-design/> (Accessed 25 June 2026)