



Prifysgol Cymru
Y Drindod Dewi Sant
University of Wales
Trinity Saint David

Project Management

LCBB5005

Table of Contents

Introduction	2
Google's UK Headquarters Project Evaluation	3
Budget Management	3
Time Management.....	3
Quality Management	4
Stakeholder Management.....	4
Risk Management	5
Scope Management	5
Integration Management.....	6
Impact on the UK's IT Sector	7
Innovation and Sustainability	7
Economic and Technological Impact.....	7
Project Management Challenges	7
Community Integration	7
Reputation and Confidence	8
Similar Projects	9
Apple's Battersea Power Station HQ	9
Meta's Kings Cross HQ	10
The Tulip	10
Conclusion	11
References	12

Introduction

In 2018 Google gave start to the construction of their massive new headquarters located in London's King's Cross area. With its astounding size of 11 floors, 330 metres in length and covering 990,000 m² of land, the building will allocate 4,400 m² for retail businesses on its ground floor and provide 76,000 m² of office space to other companies in addition to those that Google will use. Despite the numerous issues that the project has encountered, predominantly due to the global COVID-19 pandemic pushing the completion date, the project will be finished in 2024 (Gilchrist, 2022). This project is considered to be one of the biggest construction projects in Britain's history, it has had already a significant impact on many industries and businesses during its construction and it is expected to have an even bigger impact upon its completion upon the economic, ecological and business landscape particularly in London. In order to examine the scope of this project and its effects on the UK's society and businesses, this essay will focus on evaluating the management outcome of the project and if it could be considered a successful project, analysing its impact on the UK's IT sector, and reporting on the general outcome of the project and similar projects like it, and it will conclude with suggestions for future projects and a justification for the writer's stance.



Image Source: (<https://www.stevesnewsletter.com/p/londons-landscaper>)

Google's UK Headquarters Project Evaluation

In order to evaluate the success of this project, several aspects of PMBOK will be used to analyse the outcome in different project management fields.

Budget Management

The original budget for the Google Headquarters project in London was around £1 billion. Nonetheless, like numerous other extensive building initiatives, this budget was surpassed due to a mix of reasons, such as alterations to the initial design, inflation, and unexpected obstacles. Going over the budget indicates that the original cost projections were either too positive or not planned out well enough. PMBOK states that successful budget management includes accurate cost estimation, budget creation, and control mechanisms. In this instance, the budget control measures were inadequate in preventing the project from exceeding its initial financial boundaries. The incorporation of cutting-edge and eco-friendly technologies, necessary for the project's goals, also resulted in higher expenses. For example, the implementation of Building Information Modelling (BIM) was anticipated to aid in controlling costs, however, the ongoing increase in expenses suggests that these tools may not have been entirely successful. Moreover, the increase in costs indicates possible issues in the original risk evaluation or backup planning. Even with these obstacles, the project's dedication to sustainability and innovation could make the higher expenses worthwhile in the long run (Office Reality, 2022).

Time Management

Initially planned to be finished in 2024, the project has encountered several setbacks, pushing the anticipated completion date to 2025 (Accoya, 2024). Various factors, such as design changes, interruptions in the supply chain, and external events such as Brexit and the COVID-19 pandemic, have led to these delays. According to PMBOK, time management entails defining tasks, putting them in order, predicting how long they will take, and controlling the timeline. The project's timeline may have been underestimated or the scheduling methods, like the Critical Path Method (CPM), used were ineffective in dealing with the issues, as indicated by the frequent delays. The intricate nature of the project, along with the requirement for innovative building methods, played a role in the prolonged schedule. Moreover, the project timeline was additionally prolonged by external factors such as the pandemic and disruptions related to Brexit (Partridge, 2022). The issues that the project has faced so far, adding additional costs due to the delays, could affect other similar major projects in the UK.

Quality Management

A key priority of the Google Headquarters project has been to uphold rigorous quality standards, with a specific focus on sustainability and innovation. The project incorporates multiple environmentally friendly elements like a rooftop garden, solar panels, and natural ventilation systems, in line with Google's dedication to environmental stewardship. Yet, the difficulties in quality management are substantial due to the intricate nature of incorporating these characteristics. Quality management, as outlined by PMBOK, consists of quality planning, quality assurance, and quality control. The project's emphasis on sustainability necessitates strict compliance with environmental standards such as LEED or BREEAM certifications. Even though the dedication to quality is praiseworthy, the utilization of advanced materials and construction methods requires strict quality control procedures to guarantee that the end result aligns with Google's elevated criteria (CIBSE Journal, 2023).

Stakeholder Management

The Google Headquarters project includes a wide range of individuals and groups, such as Google, project managers, contractors, the local government, the King's Cross community, and environmental organizations (Hern, 2017). Efficiently managing stakeholders is essential to ensure that these different interests are in line with the project's goals. Nevertheless, the intricacy of these connections has resulted in disputes and setbacks, especially in obtaining planning permissions and meeting public demands. As indicated by PMBOK, stakeholder management consists of recognizing stakeholders, strategizing engagement, controlling expectations, and overseeing stakeholder participation. Handling Google's expectations during the Google Headquarters project has proven to be quite difficult, as the company strives to find a middle ground between innovation and sustainability while considering the realities of construction. Furthermore, the project has sparked worries among local government and community stakeholders regarding how it will affect the King's Cross area, specifically in terms of its environmental repercussions and possible employment prospects. Effectively handling these relationships is crucial in obtaining the needed assistance and preventing possible disputes that could hinder the project's progress.

Risk Management

The Google Headquarters project is exposed to various risks, such as financial, technical, operational, and environmental hurdles. The introduction of advanced technologies and materials raises the level of unpredictability, potentially causing unforeseen challenges in the construction process. Moreover, the project has been further complicated by external factors such as regulatory changes and economic conditions (Neate & Parrtridge, 2020). As per PMBOK, risk management includes recognizing risks, evaluating them, devising responses, and overseeing them. For the Google Headquarters project, it seems that the risk management strategies did not adequately foresee or address these challenges. The protests that occurred after Google's downsizing because of layoffs demonstrate the operational risks that come with a project of such high visibility. The risk management strategies for the project needed more thorough contingency plans to handle these possible issues. Adapting to new risks and reducing their effects is essential for staying on schedule and achieving success in the project.

Scope Management

Managing the scope is crucial to ensure that the Google Headquarters project achieves its desired results without any unnecessary alterations or extensions. The extensive nature of the project, which encompasses office space, amenities, and eco-friendly technologies, has presented significant difficulties in preserving project boundaries. Scope creep, which occurs when the project's boundaries grow without additional resources allotted, has been a significant issue. As per PMBOK, scope management involves planning, defining, verifying, and controlling the project's scope. Scope creep in the Google Headquarters project has happened because modifications were made to the building's design to meet the demands of local regulations, like those set by the Regent's Canal Conservation Area Advisory Committee (Waite, 2017). It is essential to manage the project's scope effectively to keep it on track with its primary goals and prevent distractions from extra requests. In order to prevent similar issues in future large-scale projects, it will be crucial for the IT sector in the UK to retain control over project scope.

Integration Management

Integration management entails ensuring that every aspect of the Google Headquarters project is efficiently synchronized and in line with the project's overarching objectives. The project necessitates coordinating different parts like design, construction, stakeholder management, and quality control. Managing this integration is made more complex by the participation of numerous contractors, designers, and stakeholders (Indeed, 2024). As per PMBOK, integration management involves generating the project charter, crafting the project management plan, supervising and executing project tasks, and overseeing project advancement. For the Google Headquarters project, advanced technologies such as BIM were utilized to enhance coordination. Nevertheless, it appears that the tools were not utilized efficiently considering the setbacks in the project's schedule and budget. Making sure integration management is efficient is crucial for completing complicated projects on schedule and within budget. The inadequate blending of different project components is probably one of the reasons for the project's continuous difficulties.

The Google Headquarters project in London embodies an ambitious outlook on office spaces to come, while also serving as a warning of the difficulties that come with groundbreaking, large projects. Although the project's focus on sustainability and innovation is praiseworthy and in line with the IT industry's future direction, the substantial budget overruns, delays, and stakeholder management problems cast doubt on its ultimate success. The UK's IT industry, which is ready for more expansion, should learn from this project that solid project management, efficient risk and scope management, and effective stakeholder communication are necessary for project success.

Impact on the UK's IT Sector

Although the project demonstrates many aspects of success, such as its ambition, innovation, and dedication to sustainability, it also encounters substantial challenges that limit its overall effectiveness. Henceforth, the project can be listed under mixed success and the following points will support this statement.

Innovation and Sustainability

The initiative establishes a demanding benchmark for upcoming IT infrastructure by prioritizing environmentally friendly features like rooftop gardens, solar panels, and advanced ventilation systems. This is in line with the worldwide shift towards sustainable growth and has the potential to encourage comparable initiatives in the UK, benefiting the IT industry (Spaen, 2019).

Economic and Technological Impact

The project will greatly enhance the UK's reputation as a top tech centre worldwide, drawing in skilled individuals and investments. Google's influence in London may spark development in the vicinity, generating employment opportunities and boosting the regional economy. In the field of IT, having a groundbreaking project like this establishes a standard for the size and aspiration of upcoming projects (Hunt, 2023).

Project Management Challenges

Despite these benefits, the project has faced considerable challenges including exceeding budget, delays, and managing various stakeholders. These obstacles indicate shortcomings in project planning, risk management, and implementation, serving as valuable lessons for upcoming projects. If not adequately dealt with, these issues could impact trust in carrying out extensive IT infrastructure projects in the UK (Wainwright, 2017).

Community Integration

Google has previously stated that the headquarters will benefit not just its employees, but also the local community. The new building will include retail spaces, a small business market hall, and community event spaces that will help create a sense of community and encourage local entrepreneurship (Prynn, 2022).

Reputation and Confidence

The project's reputation and the perceived reliability of executing similar ambitious projects in the UK could be negatively impacted by the frequent delays and exceeding budget. In the IT industry, investors and developers may become more cautious due to the risks linked to extensive projects. This concern has recently been addressed in a report by the Public Accounts Committee, requesting that the government propose a plan for dealing with this issue and better allocating the taxpayer's money (UK Parliament, 2024).

Overall, the Google HQ project in London is a groundbreaking initiative with potential long-term benefits for the UK's IT industry, yet challenges have hindered its classification as a complete success. The commendable innovative aspects of the project are overshadowed by the management challenges, pointing out areas for improvement in future initiatives. Hence, the project acts as both a source of motivation and a learning experience for the future advancement of IT infrastructure in the UK.




Image Source: (<https://www.stevesnewsletter.com/p/londons-landscaper>)

Similar Projects

Apple's Battersea Power Station HQ

Although the highly ambitious project was completed in 2023, it encountered various obstacles, largely because of the building's historical significance, the size of the project, and external factors such as the COVID-19 pandemic. Despite the delays and extra expenses, they have caused, the project still represents a major initiative that will serve as a blueprint for combining historic preservation with contemporary development (Lane, 2022).



Image Source: (<https://www.bdonline.co.uk/buildings/battersea-power-station-the-remarkable-journey-from-ruin-to-rejuvenation/5119356.article>)

Meta's Kings Cross HQ

Meta's headquarters project in King's Cross has encountered numerous obstacles, including architectural intricacies, delays in planning, the effects of the COVID-19 pandemic, and changing workplace tactics. These challenges exemplify the overall struggles of implementing extensive urban projects in ever-changing settings such as London (Carlson, 2022). Despite these obstacles, the project is still a crucial aspect of Meta's growth in the UK and will have a substantial impact on defining the future of work environments in the tech sector.



Image Source: (<https://www.bam.co.uk/how-we-do-it/case-study/meta-offices-king-s-cross>)

The Tulip

The Tulip Tower project encountered numerous obstacles, including planning denials, community resistance, environmental worries, and doubts about its financial feasibility. It was ultimately rejected due to these obstacles, demonstrating the intricate relationship between urban development, historic preservation, environmental sustainability, and public interest in a city like London. This case emphasizes the significance of ensuring that new constructions are in line with overall urban surroundings and public policy goals (BBC, 2021).



Image Source: (<https://www.bbc.co.uk/news/uk-england-london-59253160>)

Conclusion

The Google Headquarters project in London showcases the opportunities and difficulties of big, groundbreaking developments in the UK. The project has achieved a new standard for sustainability and innovation by integrating state-of-the-art technologies and environmentally friendly designs that showcase Google's dedication to environmental responsibility. These project elements are expected to benefit the UK's IT industry in the long run, boosting its international standing as a technology hub and drawing in more funding and skilled workers.

Nevertheless, the project has faced major hurdles, especially in budget control, delays, and cooperation among stakeholders. The significant budget increases and numerous postponements point out weaknesses in the project's planning and risk management procedures, causing not only a rise in expenses but also uncertainty about the project's ultimate achievement. Furthermore, the challenges in overseeing the wide range of stakeholders, such as local communities and regulatory bodies, have added complexity to the project's advancement, sparking worries about the viability of future ambitious projects.

In summary, the Google Headquarters project has seen significant accomplishments in innovation and sustainability, but its deficiencies in project management indicate that it is a partial success. The project acts as a blueprint for upcoming IT infrastructure and a warning, highlighting the importance of better planning, risk management, and stakeholder involvement in large-scale projects.



Image Source: (<https://techbehemoths.com/blog/5-largest-uk-data-centers>)

References

- Accoya, 2024. *Google HQ project update*. [Online]
Available at: <https://www.accoya.com/uk/project/google-hq-project-update/>
[Accessed 09 08 2024].
- BBC, 2021. *Tulip tower: Government rejects plans for London skyscraper*. [Online]
Available at: <https://www.bbc.co.uk/news/uk-england-london-59253160>
[Accessed 31 08 2024].
- Carlson, C., 2022. *Meta unveils King's Cross office designed by Bennetts Associates*. [Online]
Available at: <https://www.dezeen.com/2022/03/31/meta-kings-cross-office-bennetts-associates/>
[Accessed 31 08 2024].
- CIBSE Journal, 2023. *Arriving on Platform G: Google's new King's Cross office*. [Online]
Available at: <https://www.cibsejournal.com/case-studies/arriving-on-platform-g-googles-new-kings-cross-office/>
[Accessed 31 08 2024].
- Gilchrist, S., 2022. *London's Landscaper*. [Online]
Available at: <https://www.stevesnewsletter.com/p/londons-landscaper>
[Accessed 31 08 2024].
- Hern, A., 2017. *Google submits plans for 'landscaper' London headquarters*. [Online]
Available at: <https://www.theguardian.com/technology/2017/jun/01/google-submits-plans-million-sq-ft-london-hq-construction-kings-cross>
[Accessed 31 08 2024].
- Hunt, S., 2023. *Google added 1300 staff to UK workforce in 2022*. [Online]
Available at: <https://www.standard.co.uk/business/google-added-1300-staff-to-uk-workforce-in-2022-b1113752.html>
[Accessed 31 08 2024].
- Indeed, 2024. *What is integrated project management? (With a step-by-step guide)*. [Online]
Available at: <https://uk.indeed.com/career-advice/finding-a-job/integrated-project-management>
[Accessed 31 08 2024].
- Lane, T., 2022. *Battersea power station: the remarkable journey from ruin to rejuvenation*. [Online]
Available at: <https://www.bdonline.co.uk/buildings/battersea-power-station-the-remarkable-journey-from-ruin-to-rejuvenation/5119356.article>
[Accessed 31 08 2024].
- Neate, R. & Partridge, J., 2020. *Google to lease extra 70,000 sq ft in UK offices despite remote working*. [Online]
Available at: <https://www.theguardian.com/technology/2020/sep/29/google-to-lease-extra-70000-sq-ft-in-uk-offices-despite-remote-working>
[Accessed 31 08 2023].

Office Reality, 2022. *Googles new HQ costs 1 billion pounds but is it enough to tempt people back in to the office?*. [Online]
Available at: <https://www.officereality.co.uk/blog/googles-new-landscaper-hq-at-kings-cross-london-costs-1-billion-pounds-but-is-it-enough-to-tempt-people-back-in-to-the-office>
[Accessed 31 08 2024].

Partridge, J., 2022. *Behold London's 'landscaper'! Google's new UK HQ – as long as the Shard is tall*. [Online]
Available at: <https://www.theguardian.com/business/2022/jul/01/behold-londons-landscaper-googles-new-uk-hq-as-long-as-the-shard-is-tall>
[Accessed 31 08 2024].

Prynn, J., 2022. *New pictures of £1bn Google HQ bringing retail parade, community space and rooftop running trail to King's Cross*. [Online]
Available at: <https://www.standard.co.uk/homesandproperty/property-news/google-hq-new-office-kings-cross-london-plans-b994436.html>
[Accessed 31 08 2024].

Spaen, B., 2019. *Google's New Headquarters In London Focuses On Solar Energy*. [Online]
Available at: <https://www.greenmatters.com/news/2017/06/01/1aDLnU/google-london-headquarters-solar-energy>
[Accessed 31 08 2024].

UK Parliament, 2024. *UK lacks skills and capacity to deliver major infrastructure, PAC warns*. [Online]
Available at: <https://committees.parliament.uk/committee/127/public-accounts-committee/news/201373/uk-lacks-skills-and-capacity-to-deliver-major-infrastructure-pac-warns/>
[Accessed 31 08 2024].

Wainwright, O., 2017. *Sober look of Google's 'landscaper' shows tech firm is trying to grow up*. [Online]
Available at: <https://www.theguardian.com/artanddesign/2017/jun/01/sober-look-of-heatherwick-google-landscaper-shows-it-is-trying-to-grow-up>
[Accessed 31 08 2024].

Waite, R., 2017. *Heatherwick and BIG's £600m Google HQ at King's Cross set for approval*. [Online]
Available at: <https://www.architectsjournal.co.uk/news/heatherwick-and-bigs-600m-google-hq-at-kings-cross-set-for-approval>
[Accessed 31 08 2024].