

Health and Safety

1. Executive Summary	2
2. Introduction	2
3. Overview of Legislation	3
4. Impact of the Building Safety Act	3
5. Current Safety Measures in Place	3
6. Identified Hazards and Risks	4
7. Recommendations	4
8. Conclusion	4
9. Appendices	5
10. Reference	11

Health and Safety Report

Project: Affordable Flats Development, Kings Road SA1

Company: UWTSD Construction

Prepared by: Kanjou Deirki, Appointed as a trainee Health and Safety Officer for UWTSD Construction

Date: 16/11/2022



1. Executive Summary

This document summarizes the main health and safety issues related to the proposed affordable flats project at Kings Road SA1. It reviews key legal obligations, pinpoints important health and safety risks, and discusses how the Building Safety Act 2022 affects the project. The report also outlines practical recommendations to achieve full compliance and ensure a secure work environment.

2. Introduction

UWTSD Construction is set to begin the construction of a new block of affordable homes in the SA1 area. As the designated Trainee Health and Safety Officer, my goal in preparing this report is to explain how both legal and practical safety measures will be integrated throughout the project. The report focuses especially on the implications of the Building Safety Act 2022, which imposes new duties and oversight requirements, particularly impacting residential constructions.

3. Overview of Legislation

Several key pieces of legislation govern our project:

- **Building Safety Act 2022:** Sets out new roles, accountability standards, and oversight requirements for residential building projects.
- **CDM Regulations 2015:** Mandates that safety be incorporated into the design and management processes from the start through to completion.
- **Health and Safety at Work Act 1974:** Establishes the general duty to protect both workers and the public.
- **Control of Substances Hazardous to Health (COSHH) 2002:** Regulates the handling of hazardous substances.
- **Work at Height Regulations 2005:** Provides guidelines for safety when working at heights.

4. Impact of the Building Safety Act

The Building Safety Act 2022 fundamentally changes how building safety is managed in England and Wales, especially for residential properties. It introduces several new roles

and responsibilities, along with robust regulatory measures to ensure that buildings remain safe during design, construction, and occupancy.

Duty Holder Roles

Under the Act, key roles (known as duty holders) are established, with legal accountability for managing safety risks:

- **Client:** Typically, the developer or property owner, the client must ensure that all professionals involved are competent and that all legal responsibilities under the Act and CDM Regulations are met. This role also includes allocating adequate time and resources for project planning and ensuring effective collaboration among duty holders.
- **Principal Designer:** This role is responsible for overseeing health and safety during the design phase. The Principal Designer must work to minimize risks from the outset by collaborating with other designers and the Principal Contractor to integrate safe construction practices into the project plans.
- **Principal Contractor:** Tasked with managing health and safety throughout the construction phase, the Principal Contractor must plan, oversee, and verify that all work complies with legal safety standards and risk assessments, while also managing subcontractors and reporting major safety incidents.

Maintaining the Golden Thread

The “golden thread” is a continuously updated digital record of all safety-related information throughout the building’s lifecycle. This record must:

- Be accessible to everyone with responsibility for building safety.
- Be securely stored and routinely updated.
- Maintain an auditable history of decisions made during design, construction, and ongoing maintenance, including details on fire and structural safety measures, materials, and risk assessments.

Gateway Process

The Gateway Process is a critical safety review mechanism for higher-risk residential projects (typically those taller than 18 meters or seven Storeys with at least two residential units). It comprises three stages:

- **Gateway One – Planning Stage:** At this point, fire safety considerations must be integrated into the planning application. Developers need to submit a fire safety statement detailing design choices related to fire hazards.
- **Gateway Two – Pre-Construction:** Before construction begins, full design and building control approval must be secured from the Building Safety Regulator, including detailed plans on construction methods and safety management. Work cannot commence until this approval is granted.
- **Gateway Three – Completion:** Prior to occupancy, duty holders must provide final documentation to the Regulator proving that the building conforms to all approved safety measures. Only after approval will a completion certificate be issued.

Non-compliance with any gateway requirement can lead to penalties, enforcement actions, or even prevent the building from being occupied.

Safety Case and Resident Engagement

For buildings classified as higher-risk, additional requirements include:

- **Safety Case Report:** A comprehensive document that demonstrates how safety risks—such as fire hazards, structural issues, evacuation procedures, and maintenance plans—are identified and managed. This report is submitted for review by the Building Safety Regulator.
- **Resident Engagement Strategy:** Building owners are required to adopt a plan for involving residents in safety matters. This includes providing accessible safety information, encouraging feedback, and ensuring residents understand emergency procedures and their roles in maintaining a safe environment.

5. Current Safety Measures in Place

- **Site Inductions and Worker Training:** Before starting work, every person on site must complete a detailed induction covering site layout, emergency procedures, hazard recognition, and site rules. Ongoing training—such as toolbox talks and task-specific briefings—keeps everyone up to date with the latest safety practices.
- **Risk Assessments and Method Statements (RAMS):** Detailed RAMS documents are prepared for all high-risk tasks (e.g., working at heights, excavations, lifting operations) to identify hazards, assess risk levels, and define control measures. These are updated regularly to reflect site changes.

- **Mandatory Personal Protective Equipment (PPE):** The use of PPE (including hard hats, high-visibility clothing, gloves, safety goggles, and robust footwear) is compulsory, with additional equipment provided when required by the nature of the work. Regular checks ensure that PPE is used correctly and consistently.
- **Regular Inspections and Audits:** Both scheduled and impromptu site inspections are conducted to ensure adherence to safety policies and to identify hazards. Formal audits by experienced assessors—both internal and external—help monitor compliance, assign corrective actions, and verify their implementation.
- **Emergency Procedures:** Comprehensive emergency plans are in place for events such as fires, medical emergencies, or structural incidents. These plans include designated muster points, clearly posted emergency exits, and regular drills to ensure everyone understands their responsibilities during an emergency.
- **Subcontractor Oversight:** All subcontractors are required to undergo pre-qualification checks for their safety credentials. Once on site, they receive an induction and must demonstrate their competence through verified training and documentation, with regular monitoring ensuring ongoing compliance.

6. Identified Hazards and Risks

(Note: The original document appears to list this section without details. In your final report, you might want to include specific examples of hazards and risks identified on the project site.)

7. Recommendations

- **Clarify Higher-Risk Classification:** It is essential to determine early on whether the development qualifies as a “higher-risk” building under the Building Safety Act 2022 (typically if it exceeds 18 meters or has seven or more storeys). This classification affects regulatory requirements such as the Gateway approval process and the need for a Safety Case.
- **Early Engagement with the Building Safety Regulator:** Should the building be classified as higher risk, initiating early contact with the Building Safety Regulator is crucial. This helps streamline the approval process, identify potential issues early on, and foster a cooperative relationship with regulatory authorities.
- **Implement a Digital Record-Keeping Platform:** To ensure that the golden thread of safety information is maintained accurately throughout the building’s

lifecycle, it is recommended to adopt a secure digital platform (for example, using a Common Data Environment or a BIM-based system). This platform would store all relevant documents such as architectural plans, fire safety measures, material specifications, and inspection reports.

- **Conduct Competency Checks Regularly:** Ensure that all key stakeholders—ranging from the Principal Designer and Contractor to site supervisors and subcontractors—are regularly evaluated for competency. Continuous training and periodic checks help prevent human error and maintain high safety standards.
- **Schedule Frequent Safety Audits and Briefings:** Regular safety audits and weekly toolbox talks should be scheduled to reinforce safety practices on site, address emerging issues, and maintain open communication about safety protocols.

8. Conclusion

This report emphasizes that integrating sound health and safety practices is vital at every stage of the Kings Road SA1 project—from initial planning and design to construction and final occupancy. Adhering to the Building Safety Act 2022, CDM Regulations 2015, and other pertinent legislation not only protects workers and future residents but also reflects a broader commitment to responsible and sustainable construction practices. Moving forward, confirming the building’s risk status, establishing a reliable digital system for safety records, and ensuring ongoing competency among all involved parties are critical next steps. A proactive approach to safety, characterized by regular audits, continuous training, and thorough stakeholder engagement, will help UWTSD Construction set a benchmark for safe, compliant, and community-focused affordable housing.

9. Appendices

1. Site Layout

The site layout plan is a scaled diagram showing how the construction site will be organized. It helps ensure safety, efficient movement, and compliance with health and safety standards.

Contents:

- **Site boundaries and fencing**
- **Vehicle access and pedestrian walkways (segregated where possible)**
- **Location of welfare facilities** (toilets, canteen, drying rooms)

- **Storage areas** (materials, tools, hazardous substances)
- **Emergency assembly/muster points**
- **Fire points** (extinguishers and alarms)
- **Cranes and heavy equipment zones**
- **First aid station and defibrillator access**
- **Temporary site offices**

2. Risk Assessment Templates

These are blank or example templates used to document how risks are identified, assessed, and controlled.

Typical Template Sections:

- **Activity being assessed** (e.g., “Working at height – roofing”)
- **Identified hazards** (e.g., “fall from scaffolding”)
- **Who might be harmed** (e.g., “roofers, scaffolders”)
- **Risk rating before controls** (low, medium, high)
- **Control measures in place** (e.g., “guardrails, harnesses”)
- **Residual risk after controls**
- **Person responsible for implementing controls**
- **Date of review or re-assessment**

You might want to include specific templates for:

- Excavation work
- Lifting operations
- Use of hazardous substances
- Manual handling
- Confined spaces

3. Sample Induction Checklist

The checklist ensures that every worker has received and understood key safety information before they begin work on site.

Checklist Items May Include:

- Proof of identity and right to work
- Emergency procedures and fire points
- First aid and accident reporting
- PPE requirements and issue (helmet, boots, gloves, etc.)
- Site rules and conduct
- Welfare facilities and breaks
- Specific hazards on site
- RAMS acknowledgment
- Confirmation of received training (manual handling, working at height)
- Signed declaration from the worker and inducer

This helps protect both workers and the company from legal and safety risks.

4. Toolbox Talk Schedule

Toolbox talks are short, focused briefings delivered regularly to keep health and safety awareness high.

Schedule Example:

Week	Topic	Delivered By	Notes
Week 1	Slips, Trips, and Falls	Site Manager	Start of site prep
Week 2	Manual Handling	Supervisor	During foundation work
Week 3	Scaffold Safety	Health & Safety Officer	Pre-frame erection

Week 4	Fire Safety and Extinguishers	Fire Warden	Just before interior works begin
Week 5	Working Around Plant Equipment	Site Foreman	When heavy machinery is active

5. Gateway Flowchart (If Higher-Risk)

A visual representation of the **Gateway Process** under the Building Safety Act 2022, used to ensure compliance at each critical phase for high-rise residential buildings.

The flowchart typically includes:

- **Gateway 1 – Planning Stage**
 - Submit fire safety statement with planning application
 - Engage with fire service authorities (if needed)
- **Gateway 2 – Pre-Construction**
 - Submit full design package to Building Safety Regulator (BSR)
 - Receive BSR approval before any work begins
- **Gateway 3 – Completion**
 - Submit “as-built” documentation and safety case
 - BSR inspects site
 - Completion certificate issued before occupation

10. Reference

. Building Safety Act 2022.

<https://www.legislation.gov.uk/ukpga/2022/30/contents>

. Construction (Design and Management) Regulations 2015.

<https://www.hse.gov.uk/construction/cdm/2015/index.htm>

. Health and Safety at Work etc. Act 1974.

<https://www.hse.gov.uk/legislation/hswa.htm>

. Control of Substances Hazardous to Health Regulations 2002.

<https://www.legislation.gov.uk/uksi/2002/2677/regulation/7>

. Work at Height Regulations 2005.

Health and Safety

<https://www.hse.gov.uk/work-at-height/faqs.htm#:~:text=The%20Work%20at%20Height%20Regulations%202005%20changed%20the%20meaning%20of,a%20roof>