

Assignment Title: Fundamentals of Construction Technology

Module: Construction Technology



Prifysgol Cymru
Y Drindod Dewi Sant
University of Wales
Trinity Saint David

Prepared for:

G. Traylor

Created by:

H. Johal

Date completed:

1st May 2025

Table of Contents

	Page Number
1.0 Executive Summary	3
2.0 Offsite Construction	4
3.0 Comparisons	5
3.1 Ground Floor Comparison	5
3.1.2 Brick and Block	5
3.1.3 Structural Insulated Panel Systems (SIPS)	6-7
3.1.4 Twin Timber Frame	8-9
3.2 Window Openings	10
3.2.2 Brick and Block	10-11
3.2.3 Structural Insulated Panel Systems (SIPS)	11-12
3.2.4 Twin Timber Frame	12-13
3.3 Roof Details	14
3.3.2 Brick and Block	14-15
3.3.3 Structural Insulated Panel Systems (SIPS)	15-16
3.3.4 Twin Timber Frame	16-17
4.0 Conclusion	18
5.0 References	19

1. Executive Summary

This report has been prepared for Miss A Client, who has received planning approval to build a two-storey detached house on a level site that was previously used as farmland. A ground investigation report recommends using a raft foundation due to the site conditions. There is also a retaining wall on the south side of the plot.

The client is considering three construction methods for the build:

- Timber Twin Frame
- SIPS (Structural Insulated Panels)
- Brick and Block

As part of the planning requirements, the house must have an outer skin of stack bonded facing brick and blockwork with a smooth render finish. The house will also include insulated floors with underfloor heating, solid timber upper floors, triple-glazed aluminium windows and doors, and a metal sheet roof on raised tie trusses.

This report will:

1. Explain what offsite construction means and how it could apply to this project
2. Compare the ground floor, window opening, and roof eaves details for each construction method
3. Ensure all designs meet current Building Regulations, especially for thermal performance
4. Recommend the best construction method for the client based on the comparisons

2. Offsite Construction

Offsite construction is a method where parts of a building are made in a factory controlled environment before being transported to the construction site for final assembly (Buildoffsite,2023). It is used to save time, improve the quality of construction, and reduce on-site waste (Designing Buildings Wiki,2024)

For the two-storey detached house, offsite construction could be used in the following ways:


- Volumetric Construction - Entire rooms such as bathrooms or kitchens could be pre-built offsite and delivered fully fitted. This would speed up internal works and reduce disruption on site (MPBA,2023).
- Panelised Systems – Factory – made wall, floor, and roof panels could be produced offsite and quickly assembled on site. using Structural Insulated Panels (SIPS) would help achieve the required high insulation standards for the house (Buildoffsite,2023).
- Sub-assemblies and Components – smaller parts like the triple glazed aluminium windows, external doors and raised tie trusses could be manufactured separately and installed during construction, helping improve quality control (Designing Buildings Wiki,2024)
- Hybrid Systems – A combination of panelised walls and volumetric bathroom pods could be used to balance speed and traditional appearance. This approach would allow the home to meet planning conditions, such as the required brick and render finish, while taking advantage of factory-built quality (MPBA,2023).'

Overall, using offsite construction would help deliver a faster, better quality built that meets Miss A Client's needs and the current building regulations.

3. compare the ground floor, window opening, and roof eaves details for each construction method

3.1 Ground Floor Comparison

3.1.2 Brick and Block



Advantages


- High thermal mass supports underfloor heating efficiency (Chudley & Greeno, 2020).
- Durable and structurally sound – ideal for reclaimed land with retaining walls
- Excellent fire resistance (Emmitt & Gorse, 2018)
- Provided strong acoustic insulation (Ross, 2021).
- Matches planning requirement: stack bonded brick with smooth render

Disadvantages

- Slower construction due to on-site wet trades and weather dependency (Ross, 2021).
- Requires additional internal insulation to meet modern thermal performance
- Labour intensive, potentially increasing costs (Emmitt & Gorse, 2018).
- Less compatible with offsite manufacturing

- Heavier structure increases load on raft foundation
- On-site work may lead to greater disruption and waste

3.1.3 Structural Insulated Panel Systems (SIPS)



Advantages


- Excellent thermal performance due to rigid insulation core – helps meet and exceed Part L requirements with minimal additional insulation. (Borer & Harris, 2013).

- Speed up construction time significantly – panels are factory made and quickly assembled on-site, ideal for offsite construction.
- Lightweight structure reducing the load on raft foundation, which is beneficial for a reclaimed site.
- Airtightness is high – contributes to low energy consumption and supports the performance of underfloor heating.
- Precision factory fabrication results in minimal waste and high quality control.

Disadvantages

- Higher initial material cost compared to traditional methods, although this can be offset by faster build time and reduced labour costs. (Borer & Harris, 2013).
- On-site design changes are difficult once panels are manufactured – requires very accurate design and coordination early on.
- Limited flexibility during construction if issues arise, especially in custom builds.
- Fire resistance depends on internal lining and protection, unlike masonry which is inherently fireproof. (Emmitt & Gorse, 2018).
- While the internal performance is excellent, meeting planning requirements for an outer brick/render appearance may require additional cladding or façade treatments.

3.1.4 Twin Timber Frame



Advantages


- Excellent thermal insulation performance when combined with modern insulation materials — ideal for improving the building's fabric efficiency (Emmitt & Gorse, 2018).
- Lightweight system that places minimal load on the raft foundation, making it suitable for the reclaimed site conditions.
- Quicker to erect than brick and block as timber panels can be partially prefabricated and installed in sections on-site (Chudley & Greeno, 2020).
- More flexible than SIPS — allows easier adjustments and detailing during construction, such as around openings or service zones (Ross, 2021).
- Compatible with offsite construction through pre-fabricated framing elements, helping reduce on-site waste and labour time (Borer & Harris, 2013).
- Performs well in terms of airtightness and thermal bridging control, especially when paired with additional insulation boards in the internal battened zone.

Disadvantages

- Timber is less durable and fire-resistant than masonry unless properly treated and protected (Emmitt & Gorse, 2018).
- Susceptible to moisture, rot and pest damage if not well detailed or maintained — critical to get weatherproofing right.
- May require additional acoustic insulation layers to match the sound performance of heavier systems like brick and block (Chudley & Greeno, 2020).
- Depending on sourcing, timber can be environmentally intensive if not from certified sustainable sources (BRE, 2010).
- Requires careful junction detailing to ensure weather tightness at roof eaves, windows, and ground wall interfaces — especially under a metal sheeted roof system.

3.2 Window Openings

3.2.2 Brick and Block



Advantages:


- Brick and block structures provide rigid and stable openings for window frames, reducing the risk of movement or distortion over time (Chudley & Greeno, 2020).
- Suitable for supporting heavy, triple-glazed aluminium units, which is ideal for the client's design (Emmitt & Gorse, 2018).
- Traditional cavity closer systems are well understood and readily available, simplifying compliance with Building Regulations (Ross, 2021).

Disadvantages

- Risk of thermal bridging around window reveals if insulation is not correctly returned into the cavity (Chudley & Greeno, 2020).
- Labour-intensive cavity closers and wet trade finishing increase construction time (Emmitt & Gorse, 2018).

- Movement between masonry and aluminium frames may cause cracking in the surrounding render finish (BRE, 2010).

3.2.3 Structural Insulated Panel Systems (SIPS)



Advantages


- Factory-cut window openings allow for high precision, reducing gaps and improving airtightness (BRE, 2010).
- Panelised system allows quick installation of pre-prepared window zones, speeding up the build process (Borer & Harris, 2013).
- Thermal continuity around windows is easier to maintain with integrated insulated panel cores (Ross, 2021).

Disadvantages

- Errors in factory dimensions can lead to costly delays or poor fits if windows or frames arrive misaligned (Emmitt & Gorse, 2018).
- Requires additional support backing to secure heavy triple-glazed aluminium frames due to limited fixing depth (Ross, 2021).

- Achieving weatherproof connections between SIPs and external brick cladding needs careful membrane detailing (Chudley & Greeno, 2020).

3.3.4 Twin Timber Frame



Advantages


- Timber offers flexibility for on-site adjustments, useful when fine-tuning window openings (Ross, 2021).
- Easily integrates with internal insulation layers and service zones to wrap around openings, improving thermal performance (Emmitt & Gorse, 2018).
- Compatible with membrane-based airtightness detailing at junctions and reveals (Borer & Harris, 2013).

Disadvantages

- Timber can warp or shrink, potentially affecting long-term alignment of window frames if not properly treated (Chudley & Greeno, 2020).
- Heavier window units may need reinforced structural framing within the timber studwork (Ross, 2021).
- Airtightness and weather sealing require precise installation of membranes and tapes, increasing labour complexity (BRE, 2010).

3.3 Roof Details

3.3.2 Brick and Block




Advantages

- Compatible with traditional raised tie trussed rafter systems, providing structural stability and clear roof spans (Chudley & Greeno, 2020).
- Brick and block walls can easily support roof loadings, reducing the need for additional bracing (Emmitt & Gorse, 2018).
- Masonry provides excellent thermal mass, helping reduce overheating in summer and retaining heat in winter (Ross, 2021).

Disadvantages

- Wet trades increase construction time and weather dependency, which may delay roof installation (BRE, 2010).
- Brickwork shrinkage and thermal movement can cause cracking at wall-plate level if not correctly detailed (Emmitt & Gorse, 2018).
- Detailing for insulation continuity at the eaves junction must be carefully managed to avoid cold bridges (Chudley & Greeno, 2020).

3.3.3 Structural Insulated Panel Systems (SIPS)



Advantages


- SIP roofs can form structural roof panels themselves, reducing or eliminating the need for trusses in some cases (BRE, 2010).
- Continuous insulation within SIPs allows for excellent thermal performance and airtightness, especially at eaves and ridges (Ross, 2021).
- Quick to install with factory-prepared profiles, ideal for time-sensitive domestic projects (Borer & Harris, 2013).

Disadvantages

- Requires specialist lifting equipment and trained installers for placing large roof panels (Emmitt & Gorse, 2018).
- Penetrations for ventilation, services, or fastenings must be carefully sealed to preserve airtightness (BRE, 2010).
- SIP roof panels can be less breathable, increasing reliance on mechanical ventilation for roof space moisture control (Ross, 2021).

3.3.4 Twin Timber Frame

Twin Timber Roof detail



- Timber construction integrates easily with prefabricated raised tie trussed rafters, allowing quick on-site assembly (Chudley & Greeno, 2020).

- Timber roof voids provide space for service runs and additional insulation above ceiling level (Emmitt & Gorse, 2018).
- Roof-to-wall connections can be effectively sealed with membranes and tapes for airtight construction (Borer & Harris, 2013).

Disadvantages

- Timber is more susceptible to moisture and insect attack, requiring treatment and proper detailing (Ross, 2021).
- May require additional bracing and lateral restraint depending on span and wind loads (Chudley & Greeno, 2020).
- Detailing for fire resistance and sound insulation at ceiling level can be more complex than masonry construction (Emmitt & Gorse, 2018).

4.0 Conclusion

It is advised that the client move forward with the SIPS construction method for her new domestic two-story home following a thorough evaluation of the three construction methods: Brick and Block, Structural Insulated Panels (SIPS), and Timber Twin Frame.

Significant benefits are provided by SIPS in terms of airtightness, construction speed, and thermal performance, all of which complement the scenario's

design elements. A high-performance thermal envelope is required for the installation of triple-glazed aluminum windows, underfloor heating, and a metal profile roof system.

SIPS's continuous insulation and accurate factory-built detailing make it the best option for promoting energy efficiency, lowering heat loss at intersections, and streamlining the construction process on reclaimed sites where quality control and predictability are crucial (BRE, 2010; Ross, 2021).

Although brick and block construction is a reliable and well-known technique, its lengthier construction durations and dependence on wet trades are drawbacks. Similar to SIPS, Timber Twin Frame offers flexibility and ease of on-site alteration; however, it lacks thermal continuity and may need more thorough weatherproofing at the intersections of windows and roofs (Emmitt & Gorse, 2018).

References

Buildoffsite (2023)

<https://www.buildoffsite.com/content-hub/what-is-offsite-construction/>

Last Accessed 09/04/2025

Designing Buildings Wiki (2024)

https://www.designingbuildings.co.uk/wiki/Off-site_construction

Last Accessed 09/04/2025

MPBA (2023)

<https://mpba.biz/introduction-to-offsite-construction/>

Last Accessed 09/04/2025

Borer, P. and Harris, C. (2013)

<https://www.greenbooks.co.uk/the-whole-house-book>

Last Accessed 10/04/2025

BRE (2010)

<https://www.bregroup.com/sustainable-construction/sips-guide/>

Last Accessed 10/04/2025

Chudley, and Greeno (2020)

<https://www.routledge.com/Building-Construction-Handbook/Chudley-Greeno/p/book/9780367204749>

Last Accessed 10/04/2025

Emmitt and Gorse (2018)

<https://www.wiley.com/en-gb/Barry%27s+Introduction+to+Construction+of+Buildings%2C+4th+Edition-p-9781118977100>

Last Accessed 10/04/2025

Ross, K (2021)

https://www.ribabooks.com/Modern-Methods-of-Construction-A-Practical-Guide-2nd-edition_9781859469793

Last Accessed 10/04/2025