



Prifysgol Cymru
Y Drindod Dewi Sant
University of Wales
Trinity Saint David

Applying Project Management Techniques (ACEA 7009)

Module – Managing Engineering Projects

Lecturer – Andrew Thorn

Jordan Randel – 1551653

Table of Figures

Figure 1 - Network Diagram Node Example	5
Figure 2 - Network Diagram Activities	5
Figure 3 - Project Network Diagram	6
Figure 4 - Project Gantt Chart.....	7
Figure 5 - PERT Analysis	10
Figure 6 – Project Activity Cost Breakdown.....	11
Figure 7 - Crash Costed Project Activity Cost Breakdown	12
Figure 8 - Crash Costed Activities.....	13

Table of Figures

Equation 1 - PERT Formula	9
---------------------------------	---

Table of Contents

Table of Figures	2
Table of Figures	2
Introduction.....	4
Project Network Diagram	5
Gantt Chart.....	7
Role of Communication.....	8
Program Evaluation and Review Technique (PERT) Analysis	9
Project Activity Cost Breakdown	11
Crash Costing.....	12
Considering Project Handover Issues	14
Conclusion	16
References.....	17

Introduction

In the realm of modern project management, the ability to seamlessly coordinate complex endeavours such as the construction of a mine water treatment plant requires both technical expertise and a comprehensive understanding and application of diverse project management techniques. This report examines the development of such a project, serving as a practical demonstration of various methodologies and strategies employed to ensure its successful execution. The focal points of this report encompass a wide spectrum of project management features, each contributing to the holistic management of the endeavour.

A thorough construction network diagram and Gantt chart will be meticulously crafted to define individual activities and determine the critical path, providing a roadmap for project implementation and resource allocation. Communication plays a pivotal role in project management, it will be scrutinised, emphasising its significance in fostering synergy among stakeholders, mitigating misunderstandings, and ensuring alignment with the construction objectives of the mine water treatment plant.

An assessment of potential risks inherent in the project is conducted, accompanied by a strategic discourse on risk mitigation techniques. Various methodologies for risk management are explored, offering insights into proactive measures to safeguard project outcomes.

The cost implications of individual activities and the cumulative expenses of the entire project will be analysed, shedding light on the financial dimensions of project execution, and providing a basis for informed decision-making. Through the application of crash costing techniques, efforts are directed towards compressing the project timeline, demonstrating the pragmatic utilisation of resource optimisation strategies to expedite the project delivery without compromising quality.

Anticipating the transition from project completion to operational phase, considerations regarding project handover are reflected upon, highlighting the importance of seamless knowledge transfer and stakeholder engagement in ensuring sustained project success.

Project Network Diagram

The mine water treatment plant activities table is shown in figure 2. The network diagram, shown in figure 3, visually represents the sequence of activities and their durations required to complete the construction of the water treatment plant. By mapping out the relationships between different project tasks, dependencies, and durations, this diagram provides a comprehensive overview of the project schedule and critical path, which is shown in red.

Figure 1 is an example that helps in explaining that each activity is represented by a node, and the arrows between nodes indicate the sequence in which the activities must be completed, the duration of each activity is shown next to the arrow. The float, forward and backward pass is shown within the node as well as the activity (Mujumdar & Maheswari, 2019).. By following the flow of activities and identifying critical paths, project managers can effectively allocate resources, monitor progress, and mitigate potential delays or bottlenecks.




Figure 1 - Network Diagram Node Example

Activity	Duration (days)
O-A	5
A-B	10
B-C	2
B-D	3
C-E	7
D-E	7
E-F	16
F-G	22
G-H	5
H-I	7
I-J	5
H-K	8
K-L	5
L-M	27
J-M	27
M-N	15
N-O	1
O-P	2
Q-P	2
N-Q	8
N-R	5
N-S	20
R-T	8
S-T	8
T-U	15
U-V	10
U-W	12
W-X	13
W-Y	15
W-Z	20
X-AA	3
Y-AA	3
Z-AA	3
AA-AB	5
S-AC	15
AC-AD	10
AB-AE	12
AD-AE	12
AE-AF	5
AF-AG	1
AG-AH	21
AH-AI	3
AH-AJ	8
AI-AK	1
AJ-AK	1
AG-AL	15
AK-AM	3
AL-AM	3

Figure 2 - Network Diagram Activities




Figure 3 - Project Network Diagram

Gantt Chart

A key aspect to a successful project is in the planning, it is often the first thing that is considered. The proposed project schedule is presented in figure 4 in the form of a Gantt chart. The Gantt chart lists all the activities within the construction of the mine water treatment plant. It also lists how long each of the activities will take in number of days as well as dates for starting and finishing each task. The initial project schedule spans over 11 months however a tolerance of +/- 10% has been set.




Figure 4 - Project Gantt Chart

Role of Communication

Managing a project such as the construction of a mine water treatment plant has many technical challenges. The managing of multiple contractors of various skills and trades requires highly effective communication to ensure coordination, collaboration, and successful project delivery.

Communication is essential for coordinating the activities of multiple contractors working on different aspects of the project from mechanical, through to civils and electrical as well as building confidence and trust with all contractors (Doloi, 2009). Clear communication channels are required to ensure that each contractor understands their role, responsibilities, and timelines, preventing conflicts and overlapping work. Construction projects often have tight schedules, without much slack time so effective communication is crucial for keeping the project on track. Regular updates on progress, potential delays, and schedule adjustments allow project managers to make informed decisions and allocate resources efficiently. Regular progress reports, meeting minutes, and formal documentation of contractual agreements help mitigate risks and provide a record of project activities to the stakeholders.

Clear communication of standards and expectations regarding quality are essential to ensure that all contractors adhere to the project's quality standards (Parker, et al., 2017). Regular inspections, feedback loops, and reporting mechanisms help identify and address quality issues promptly. Construction sites are inherently risky environments, as multiple contractors are working together on site with heavy machinery, increased height hazards, unstable structures, and hazardous materials. Effective communication is vital for ensuring safety compliance among contractors. Clear safety protocols, hazard assessments, and emergency procedures need to be communicated and enforced consistently through the project as new hazards present themselves.

Construction projects often encounter changes due to unforeseen circumstances, design modifications, client requests, or general project changes. Effective communication channels allow for the timely communication of change orders, approvals, and any associated impacts on the project schedule and budget. Any deviations from the original plan are clearly communicated to ensure client satisfaction (Saxena & McDonagh, 2022).

With multiple contractors involved, conflicts are bound to arise, whether due to differing opinions, competing priorities, or resource constraints. Effective communication skills are crucial for resolving conflicts diplomatically, finding mutually acceptable solutions to maintain a positive working relationship among contractors (Zulch, 2016).

Effective communication fosters a culture of knowledge sharing and continuous improvement among contractors. Lessons learned from past experiences, best practices, and innovative ideas can be shared to enhance the overall performance and efficiency of the project.

Program Evaluation and Review Technique (PERT) Analysis

The PERT analysis will examine the network of critical path activities involved in the constructing the water treatment plant, their estimated durations, and the dependencies between these activities. By applying the principles of PERT, the critical path is identified which represents the sequence of activities with the longest duration and determines the minimum project duration. Critical activities are those that, if delayed, would extend the overall project duration. By analysing the estimated durations of each activity and their interdependencies, the overall project schedule can be evaluated and opportunities to streamline workflow, optimise resource allocation, or minimise project duration can be identified. The identified non-critical activities can be fast-tracked or crashed to achieve a balance between project time, cost, and quality objectives.

PERT analysis enables us to assess the impact of uncertainties and risks on project schedule and identify contingency plans to mitigate potential delays. Activities with well-defined contingency plans may be considered less risky compared to those without adequate risk mitigation measures in place. By considering optimistic, pessimistic, and most likely time estimates for each activity, the project risks can be managed and better anticipated. If there is significant variability between the optimistic, most likely, and pessimistic time estimates for an activity, it indicates a higher level of uncertainty. A wider range of estimates suggests that the activity's duration is more unpredictable and potentially riskier. The PERT value is a weighted average of the optimistic, most likely, and pessimistic time estimates, with more weight given to the most likely estimate. If the most likely estimate differs significantly from the optimistic and pessimistic estimates, it can affect the accuracy of the PERT value and indicate higher risk. Activities with complex dependencies or rely on external factors beyond the project team's control are inherently riskier. Delays or disruptions in upstream activities can cascade downstream, impacting the overall project schedule and increasing the risk associated with individual activities (Liu, 2013).

The insights gained from PERT analysis provide project stakeholders with valuable information for making informed decisions regarding project scheduling, resource allocation, and risk management. Stakeholder can better understand the project's complexities and dependencies by visualising the project network and critical path (Turan & Asar, 2020).

PERT Time for each activity is calculated using the formula shown in equation 1. The activities optimistic, most likely, pessimistic and PERT value are shown in figure 5.

$$\text{PERT Time} = \frac{(O+4ML+P)}{6}$$

Equation 1 - PERT Formula

Activity	Optimistic	Most Likely	Pessimistic	PERT Value
O	-	5	-	-
A-B	8	10	12	10.00
B-C	1.5	2	4	2.25
B-D	2	3	5	3.17
D-E	5	7	10	7.17
E-F	12	16	18	15.67
F-G	17	22	25	21.67
G-H	5	5	5	5.00
H-I	5	7	10	7.17
I-J	5	5	5	5.00
H-K	6	8	10	8.00
K-L	5	5	5	5.00
J-M	20	27	30	26.33
M-N	10	15	17	14.50
N-O	1	1	1	1.00
O-P	1	2	2	1.83
N-Q	5	8	10	7.83
N-R	4	5	8	5.33
N-S	15	20	22	19.50
S-T	5	8	10	7.83
S-U	10	15	17	14.50
U-V	6	10	12	9.67
U-W	8	12	15	11.83
W-X	10	13	15	12.83
W-Y	10	15	17	14.50
W-Z	12	20	23	19.17
Z-AA	2	3	4	3.00
AA-AB	1	5	5	4.33
S-AC	10	15	15	14.17
AC-AD	3	10	10	8.83
AD-AE	10	12	12	11.67
AE-AF	3	5	8	5.17
AF-AG	1	1	1	1.00
AG-AH	21	21	21	21.00
AH-AI	2	3	3	2.83
AH-AJ	8	8	8	8.00
AJ-AK	1	1	1	1.00
AG-AL	8	15	17	14.17
AL-AM	2	3	4	3.00

Figure 5 - PERT Analysis

Some of the activities can be seen as riskier than others due to the estimated difference between the optimistic and pessimistic values. Some of the larger differences are the tasks that will take longer. Critical activities can be prioritised by crash costing to ensure that the project meets the deadline set out. Some tasks such as the harmonic survey, activity AG-AH, for 21 days are fixed, there is no risk of delays or of completing early. Slack time can also be built into the project to accommodate some unexpected delays or disruptions. Another possible way of contingency planning is maintaining a reserve of critical resources, such as skilled labour, materials, or equipment, to address unexpected shortages or delays in procurement. Regular risk assessments and scenario planning should be undertaken to identify potential risks and develop mitigation strategies. Clear communication channels and protocols are to be established for disseminating information to project stakeholders in the event of unexpected developments. Quality control measures and inspections need to be implemented to identify and rectify defects or deficiencies early in the project lifecycle. Establishing a quality assurance team or process to monitor compliance with project specifications and standards.

Project Activity Cost Breakdown

In the breakdown, shown in figure 5, of the mine water treatment plant costs, the expenses regarding each of the activities involved have been broken down into a material/hire cost and labour cost to provide a comprehensive understanding of where resources are allocated. This breakdown serves as a vital tool for stakeholders, enabling informed decision-making and strategic resource allocation.

The costing also lists the estimated number of personnel that is required to conduct each task as well as average rates depending on whether there will be any work undertaken outside of normal working hours. The total cost for the project is estimated to be approximately £733,250, a tolerance of +/- 5% has been set.

Project		Mine Water Treatment Plant								
Item No	Activity Description	Material/Plant Hire Cost	Labour Hours	Std Hours	OT1 Hours x1.5 Rate	OT2 Hours x2 Rate	Labour Grade	Labour Chargeout Rate (Average)	Labour Cost	Total Chargeout
1	Pre-Condition Survey	£850.00	40.00	40.00			Chartered Surveyor	£139.10	£5,564.00	£6,414.00
2	Site Fencing & Signage	£3,400.00	64.00	64.00			Labourer	£40.66	£2,602.24	£6,002.24
3	Welfare & Storage	£12,300.00	96.00	96.00			Site Service Fitters	£51.90	£4,981.92	£17,281.92
4	Site Inductions	£500.00	40.00	40.00			Principal Contractor	£101.65	£4,066.00	£4,566.00
5	Vegetation Clearance	£5,200.00	168.00	168.00			Grounds Worker	£52.43	£8,808.24	£14,008.24
6	Excavation Works	£8,200.00	384.00	384.00			Grounds Worker	£52.43	£20,133.12	£28,333.12
7	Construct Piles	£11,600.00	704.00	704.00			Piledriver	£44.41	£31,261.12	£42,861.12
8	Curing	£1,100.00		-				-	-	£1,100.00
9	Ground Floor Slab	£8,250.00	280.00	280.00			Civils Contractors	£56.71	£15,878.80	£22,128.80
10	Curing	£1,100.00		-				-	-	£1,100.00
11	Sump & Plinth Install	£5,700.00	256.00	256.00			Civils Contractors	£56.71	£14,517.76	£20,217.76
12	Curing	£1,100.00		-				-	-	£1,100.00
13	Erection of Structure	£28,200.00	1,728.00	1,728.00			Civils Contractors	£56.71	£97,994.88	£126,194.88
14	Cladding	£14,300.00	480.00	480.00			Roofers/Cladding Ins taller	£44.94	£21,571.20	£35,871.20
15	Generator Delivery	£500.00		-				-	-	£500.00
16	Generator Connection	£1,200.00	16.00	16.00			E & I Technician	£56.71	£907.36	£2,107.36
17	Panel Delivery & Install	£3,600.00	256.00	256.00			E & I Technician	£56.71	£14,517.76	£18,117.76
18	Inlet Pumps Install	£8,200.00	160.00	160.00			Mechanical Fitter	£51.90	£8,303.20	£16,503.20
19	Reaction Tanks Install	£17,300.00	640.00	640.00			Mechanical Fitter	£51.90	£33,212.80	£50,512.80
20	Sludge Tank & Dry Cake Storage Install	£7,100.00	192.00	192.00			Mechanical Fitter	£51.90	£9,963.84	£17,063.84
21	Main Pipes Install	£16,250.00	480.00	480.00			Mechanical Fitter	£51.90	£24,909.60	£41,159.60
22	Site Lighting Install	£8,600.00	320.00	320.00			E & I Technician	£56.71	£18,147.20	£26,747.20
23	Instrumentation Install	£15,400.00	288.00	288.00			E & I Technician	£56.71	£16,332.48	£31,732.48
24	Small Bore Pipework	£7,800.00	208.00	208.00			E & I Technician	£56.71	£11,796.68	£19,596.68
25	Containment Install	£9,300.00	240.00	240.00			E & I Technician	£56.71	£13,610.40	£22,910.40
26	Cabling Install	£15,600.00	800.00	800.00			E & I Technician	£56.71	£45,368.00	£60,968.00
27	Cable Testing	£700.00	48.00	48.00			E & I Technician	£56.71	£2,722.08	£3,422.08
28	Snagging	£1,500.00	160.00	160.00			E & I Technician	£56.71	£9,073.60	£10,573.60
29	Commissioning Plan		120.00	120.00			Commissioning Engineer	£104.86	£12,583.20	£12,583.20
30	Commissioning Plan Approval			-				-	-	-
31	Cold Commission	£1,500.00	192.00	192.00			Commissioning Engineer	£104.86	£20,133.12	£21,633.12
32	Hot Commission	£1,500.00	80.00	80.00			Commissioning Engineer	£104.86	£8,388.80	£9,888.80
33	Swap Generator & DNO	£850.00	8.00	8.00			E & I Technician	£56.71	£453.68	£1,303.68
34	Harmonic Survey	£3,200.00	24.00	24.00			E & I Technician	£56.71	£1,361.04	£4,561.04
35	Welfare Facilities Removal	£2,400.00	72.00	72.00			Site Service Fitters	£51.90	£3,736.44	£6,136.44
36	Training	£800.00	80.00	80.00			Commissioning Engineer	£104.86	£8,388.80	£9,188.80
37	Demobilisation	£2,100.00	24.00	24.00			Labourer	£40.66	£975.84	£3,075.84
38	As-Built Documentation	£100.00	120.00	120.00			Project Manager	£90.96	£10,914.00	£11,014.00
39	Handover	£400.00	48.00	48.00			Project Manager	£90.96	£4,365.60	£4,765.60
40				-				-	-	-
Summary										Sheet Total
										£733,243.80

Figure 6 – Project Activity Cost Breakdown

Crash Costing

Transitioning into the application of crash costing techniques to expedite project completion by at least seven days, the focus shifts towards optimising resource allocation and scheduling to meet time constraints. The emphasis lies on identifying activities to strategically allocate additional resources to streamline workflows without compromising quality or safety standards. Crash costing will be focused on the critical path activities, as they are crucial for determining the minimum duration of the project (Meier, et al., 2016). Before the crash costing can be implemented, it must be ensured that sufficient resources, such as manpower, equipment, and materials, are available to support the accelerated schedule. The potential impact of crashing activities on the quality of workmanship and deliverables should also be considered, poor quality can lead to rework and additional costs in the long run (Maraq, et al., 2022). Project stakeholders, including clients, team members, and suppliers, should be informed about the rationale behind crash costing decisions, potential implications, and adjustments to project timelines or deliverables. The project progress will need to be continuously monitored after implementing crash costing techniques to ensure it has been effective. Shown in figure 7, some of the activities have been crash costed by working additional hours at an overtime rate.

Project		Mine Water Treatment Plant									
Item No	Activity Description	Material/Plant Hire Cost	Labour Hours	Std Hours	OT1 Hours x1.5 Rate	OT2 Hours x2 Rate	Labour Grade	Labour Chargeout Rate (Average)	Labour Cost	Total Chargeout	
1	Pre-Condition Survey	£850.00	40.00	40.00			Chartered Surveyor	£139.10	£5,564.00	£6,414.00	
2	Site Fencing & Signage	£3,400.00	64.00	64.00			Labourer	£40.66	£2,602.24	£6,002.24	
3	Welfare & Storage	£12,300.00	96.00	96.00			Site Service Fitters	£51.90	£4,981.92	£17,281.92	
4	Site Inductions	£500.00	40.00	40.00			Principal Contractor	£101.65	£4,066.00	£4,566.00	
5	Vegetation Clearance	£5,200.00	168.00	168.00			Grounds Worker	£52.43	£8,808.24	£14,008.24	
6	Excavation Works	£8,200.00	512.00	384.00	128.00		Grounds Worker	£58.58	£29,994.24	£38,194.24	
7	Construct Piles	£11,600.00	880.00	704.00	176.00		Piledriver	£47.07	£41,420.98	£53,020.98	
8	Curing	£1,100.00		-				-	-	£1,100.00	
9	Ground Floor Slab	£6,250.00	280.00	280.00			Civils Contractors	£56.71	£15,878.80	£22,128.80	
10	Curing	£1,100.00		-				-	-	£1,100.00	
11	Sump & Plinth Install	£5,700.00	256.00	256.00			Civils Contractors	£56.71	£14,517.76	£20,217.76	
12	Curing	£1,100.00		-				-	-	£1,100.00	
13	Erection of Structure	£28,200.00	2,160.00	1,728.00	432.00		Civils Contractors	£60.78	£131,276.16	£159,476.16	
14	Cladding	£14,300.00	480.00	480.00			Roofer/Cladding Installer	£44.94	£21,571.20	£35,871.20	
15	Generator Delivery	£500.00		-				-	-	£500.00	
16	Generator Connection	£1,200.00	16.00	16.00			E & I Technician	£56.71	£907.36	£2,107.36	
17	Panel Delivery & Install	£3,600.00	256.00	256.00			E & I Technician	£56.71	£14,517.76	£18,117.76	
18	Inlet Pumps Install	£8,200.00	160.00	160.00			Mechanical Fitter	£51.90	£8,303.20	£16,503.20	
19	Reaction Tanks Install	£17,300.00	800.00	640.00	160.00		Mechanical Fitter	£67.30	£53,842.40	£71,142.40	
20	Sludge Tank & Dry Cake Storage Install	£7,100.00	192.00	192.00			Mechanical Fitter	£51.90	£9,963.84	£17,063.84	
21	Main Pipes Install	£16,250.00	480.00	480.00			Mechanical Fitter	£51.90	£24,909.60	£41,159.60	
22	Site Lighting Install	£8,600.00	320.00	320.00			E & I Technician	£56.71	£18,147.20	£26,747.20	
23	Instrumentation Install	£15,400.00	288.00	288.00			E & I Technician	£56.71	£16,332.48	£31,732.48	
24	Small Bore Pipework	£7,800.00	208.00	208.00			E & I Technician	£56.71	£11,795.68	£19,595.68	
25	Containment Install	£9,300.00	240.00	240.00			E & I Technician	£56.71	£13,610.40	£22,910.40	
26	Cabling Install	£15,600.00	1,000.00	800.00	200.00		E & I Technician	£60.11	£60,112.60	£75,712.60	
27	Cable Testing	£700.00	48.00	48.00			E & I Technician	£56.71	£2,722.08	£3,422.08	
28	Snagging	£1,500.00	160.00	160.00			E & I Technician	£56.71	£9,073.60	£10,573.60	
29	Commissioning Plan		120.00	120.00			Commissioning Engineer	£104.86	£12,583.20	£12,583.20	
30	Commissioning Plan Approval			-				-	-	-	
31	Cold Commission	£1,500.00	192.00	192.00			Commissioning Engineer	£104.86	£20,133.12	£21,633.12	
32	Hot Commission	£1,500.00	80.00	80.00			Commissioning Engineer	£104.86	£8,388.80	£9,888.80	
33	Swap Generator & DNO	£850.00	8.00	8.00			E & I Technician	£56.71	£453.68	£1,303.68	
34	Harmonic Survey	£3,200.00	24.00	24.00			E & I Technician	£56.71	£1,361.04	£4,561.04	
35	Welfare Facilities Removal	£2,400.00	72.00	72.00			Site Service Fitters	£51.90	£3,736.44	£6,136.44	
36	Training	£800.00	80.00	80.00			Commissioning Engineer	£104.86	£8,388.80	£9,188.80	
37	Demobilisation	£2,100.00	24.00	24.00			Labourer	£40.66	£975.84	£3,075.84	
38	As-Built Documentation	£100.00	120.00	120.00			Project Manager	£90.95	£10,914.00	£11,014.00	
39	Handover	£400.00	48.00	48.00			Project Manager	£90.95	£4,365.60	£4,765.60	
40				-				-	-	-	
Summary										Sheet Total	
										£821,920.26	

Figure 7 - Crash Costed Project Activity Cost Breakdown

Activity	Activity Description	Normal Duration (Days)	Normal Cost per day	Normal Cost Total	Crash Cost Duration (Days)	Crash Cost per day	Crash Cost Total	Time Saved	Crash Increase
E-F	Excavation Works	16	£1,770.82	£28,333.12	14	£2,546.28	£38,194.24	2	£9,861.12
F-G	Construct Piles	22	£1,948.23	£42,861.06	20	£2,651.05	£53,020.98	2	£10,159.92
L-M	Erection of Structure	27	£4,673.88	£126,194.88	23	£6,933.75	£159,476.16	4	£33,281.28
N-S	Reaction Tanks Install	20	£2,525.64	£50,512.80	17	£4,184.85	£71,142.40	3	£20,629.60
W-Z	Cabling Install	20	£3,048.40	£60,968.00	17	£4,453.68	£75,712.60	3	£14,744.60

Figure 8 - Crash Costed Activities

The activities shown in figure 8 are the activities that were selected to be crash costed. These tasks were seen to be potentially riskier due to the length of time difference between the optimistic and pessimistic times stated. The crash cost sequence is E-F, F-G, L-M, N-S, and W-Z. By crash costing the 5 tasks, the project duration was reduced by 14 days. This means that the project will be completed earlier than originally planned, which could have several benefits such as early completion may allow the project to start generating revenue sooner as well as possible early finish rewards. It can also result in a reduction of overhead costs associated with project management and administration. Completing a project early could improve stakeholder satisfaction by meeting deadlines or contractual obligations ahead of schedule.

In this case, crashing the 5 tasks resulted in an increase in project cost by approximately £88,700. The increased cost may impact the project budget and financial viability. It's essential to ensure that the benefits of crashing, such as early completion or reduced penalties for late delivery, outweigh the additional costs incurred.

Crashing can introduce additional risks to the project, such as increased resource constraints, potential for errors or rework due to rushed work, and impact on team morale and productivity. It's important to assess these risks and implement appropriate mitigation strategies to minimize their impact on project success.

The decision to crash tasks involves a trade-off between project time and cost (Mohanty, et al., 2011). In the scenario of the mine water treatment plant, the project team decided to prioritise reducing project duration over minimising cost. Project managers must carefully evaluate the trade-offs and consider the project's overall objectives, constraints, and stakeholder priorities when deciding whether to crash tasks.

Considering Project Handover Issues

The handover of a mine water treatment plant project to the client is a critical phase that requires careful consideration and planning to ensure a smooth transition from the construction phase, usually under a contractors control, to operation and maintenance which is under the clients control.

A major consideration for project handover is to ensure that all project documentation, including plans, specifications, manuals, and as-built drawings including control philosophies, are compiled, and organised for final handover to the client. All documentation must be accurate and up to date, detailing the location and specifications of all components installed during construction. Any discrepancies between the original design and actual construction should be addressed before handover to avoid confusion during operation and maintenance. The documentation that will be required to be handed over to the client will have been detailed in the contract (Rodrigues, et al., 2024).

Provide comprehensive training for the client's operators on the use, maintenance, and troubleshooting of the water treatment plant equipment and control systems. It can be an issue ensuring that the client's staff have a thorough understanding of the plant's operation, including process control, safety protocols, and emergency procedures. To facilitate this, knowledge transfer sessions between the project team and the client's staff will need to be planned and attended to address any questions or concerns regarding the operation and maintenance of the plant. It can be difficult to plan for all relevant staff to attend these sessions so multiple sessions on separate days will need to be planned to accommodate this.

Prior to this happening, thorough commissioning and testing of all plant components and systems shall be undertaken to ensure that they are functioning correctly, meeting performance requirements and specifications. The commissioning results should be documented, certification of compliance with relevant regulatory standards and specifications needs to be provided. Any issues or deficiencies identified during commissioning needs to be addressed. In the case of the mine water treatment plant, documentation demonstrating compliance with environmental regulations, water quality standards, and other applicable laws and regulations need to be provided and need to be accurate. The client will need to be informed regarding their ongoing obligations for regulatory compliance and provide guidance on monitoring, reporting, and record-keeping requirements.

Another crucial part of the handover is to provide guidance on routine operation and maintenance tasks, including inspection schedules, equipment lubrication, and filter replacement. Informing the client of any specialised maintenance requirements for critical equipment or systems, such as pumps, and chemical dosing systems. Establishing a maintenance schedule and recommend preventive maintenance procedures to minimise downtime and extend the lifespan of equipment (Al-Saady & Rezouki, 2022).

The warranty coverage terms will need clarification for the equipment and materials as part of the project. Contact information for technical support and service providers, including emergency contact numbers and procedures for reporting and resolving issues will be provided.

Finally, a formal handover ceremony shall be coordinated to mark the completion of the project and the transfer of responsibility to the client. If this isn't completed the client may not be clear that they are now responsible. A handover package containing all relevant documentation, including manuals, warranties, permits, and certifications will be provided. To secure this, a signed acceptance from the client acknowledging receipt of the handover package and confirming their understanding of their responsibilities as the new owner/operator of the water treatment plant needs to be obtained.

Conclusion

The culmination of this report highlights the comprehensive approach required for the successful execution of a project as complex as the construction of a mine water treatment plant. Through detailed planning, effective communication, risk management, cost analysis, and strategic decision-making, the project management team can navigate through various challenges to achieve the project objectives.

The construction network diagram and Gantt chart provides a structured framework for project implementation, allowing for the efficient allocation of resources and identification of critical path activities. Strong communication skills and robust communication channels are essential for overcoming the challenges inherent in such complex projects. Clear communication channels prove to be instrumental in fostering collaboration among stakeholders, mitigating conflicts, safety compliance, change management and ensuring adherence to project timelines and quality standards. Risk assessment and mitigation strategies are systematically integrated into the project management process, enhancing resilience against potential disruptions.

Cost analysis provided valuable insights into resource allocation and budget management, while crash costing techniques demonstrated agility in responding to time constraints without compromising quality. The strategic application of PERT analysis facilitates a greater understanding of a project's complexities, enabling informed decision-making and proactive management of uncertainties.

Looking forward to the transition from project completion to the operational phase, considerations for project handover highlights the importance of comprehensive documentation, training, and maintenance protocols to ensure a seamless transfer of responsibility to the client.

In conclusion, the mine water treatment plant project serves as a testament to the value of integrated project management methodologies and the importance of adaptive leadership in navigating through dynamic project landscapes. By leveraging technical expertise, effective communication, risk management, and strategic planning, the project management team can deliver sustainable solutions that meets stakeholder expectations.

References

- Al-Saady, a. & Rezouki, S. E., 2022. Artificial Neural Network Model for Wastewater Projects Maintenance Management Plan. *Journal of Engineering*, 28(11), pp. 14-31.
- Doloi, H., 2009. Relational partnerships: the importance of communication, trust and confidence and joint risk management in achieving project success. *Construction management and economics*, 27(11), pp. 1099-1109.
- Liu, M., 2013. Program Evaluation and Review Technique (PERT) in Construction Risk Analysis. *Applied Mechanics and Materials*, Volume 357-360, pp. 2334-2337.
- Meier, C., Yassine, A. A., Browning, T. R. & Walter, U., 2016. Optimizing time–cost trade-offs in product development projects with a multi-objective evolutionary algorithm. *Research in engineering design*, 27(4), pp. 347-366.
- Mohanty, A., Mishra, J. & Satpathy, B., 2011. Activity modes selection for project crashing through deterministic simulation. *Journal of industrial engineering and management*, 4(4), pp. 610-623.
- Mujumdar, P. & Maheswari, J. U., 2019. Alternate beeline diagramming method network analysis for interdependent design entities. *Engineering, construction, and architectural managemen*, 26(1), pp. 66-84.
- Parker, D. W., Kunde, R. & Zeppetella, L., 2017. Exploring communication in project-based interventions. *International journal of productivity and performance management*, 66(2), pp. 146-179.
- Rodrigues, T. d. A. et al., 2024. Risk factor prioritization in infrastructure handover to operations. *International journal of project management*, 42(1), p. 102558.
- Saxena, D. & McDonagh, J., 2022. Communication breakdowns during business process change projects – Insights from a sociotechnical case study. *International Journal of Project Management*, 40(3), pp. 181-191.
- Turan, E. & Asar, R., 2020. Ship Repair and Maintenance Management: Application of PERT Analysis on a Tanker Vessel. *Journal of ship production and design*, 36(3), pp. 181-188.

Zulch, B., 2016. A proposed model for construction project management communication in the South African construction industry. *Acta structilia*, 23(1), pp. 1-35.